

ADDENDUM NUMBER 1
City of Avon Park
Wastewater Treatment Plant Sand & Grit Removal
ITB #21-01
March 2, 2021

1. The Contractor assumes complete responsibility for measuring, determining, and certifying that they have removed at least 80% of the Sand and Grit from tanks that currently have at least 10% by volume of Sand and Grit. The City will consult with the Contractor and share whatever information they have regarding the volume of Sand and Grit, but the Contractor is considered the expert and is therefor completely responsible for certifying the amount removed.

2. The Contractor is completely responsible for removing only Sand and Grit and thus must have an effective method for separating sludge, rags, and other material from the Sand and Grit and returning the sludge back into the oxidation ditches.