E·13

From: Dave Lance [mailto:DaveLance@Waste-Equip.com]
Sent: Tuesday, February 03, 2015 2:21 PM
To: Julian Deleon
Cc: Alan Blanchard
Subject: 2015 City of Avon Park Quote 2153.pptx

Hi Julian:

Attached for your review is our proposal for a new 2015 EZ Pack 44 Cubic Yard commercial front loader and Mack MRU chassis.

This pricing is our best pricing under the City of Tallahassee contract 2490. Included in this contract we offer leasing options and also buy back options. Please let me know if we can provided of these options.

Also please let us know if we need to make any adjustments.

Thank you,

Dave

David B. Lance
Waste Equipment & Parts LLC
813-361-8075 Direct Cell

Corp. Office
4902 South 16th Avenue, Suite E, Tampa, Florida 33619
813-241-1900 / Fax 813-241-1990

South Florida
1907 NW 40th Court, Pompano Beach, Florida 33064
954-366-5232 / Fax 954-532-7439

NOTICE: This e-mail message, including any attachments, is for the sole use of the intended recipient(s) and may contain confidential or proprietary information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient, immediately contact the sender by reply e-mail and destroy all copies of the original message.

Waste Equipment & Parts LLC
4902 South 16th Avenue, Suite E
Tampa, FL 33619

(813)241-1900
http://www.waste-equip.com

Quote

Date	Quote No.
02/03/2015	2153

Exp. Date

Address

City of Avon Park
2301 US 27 South
Avon Park, FL 33825

Sales Rep	Project
Dave Lance	Front Loader

Part Number	Description	Quantity	Price	Amount
EZ-CFL-44-2015	• EZ Pack Commercial Front Loader 44 Cubic Yard	1	94,821.00	94,821.00T
EZ-B01CFL	• 7 Ga. 100,000 PSI Body Side	1	468.00	468.00T
EZ-B02CFL	• Hopper Sump Overlay	1	282.00	282.00T
EZ-B06CFL	• Sharks Teeth (4) on Packing Panel	1	437.00	437.00T
EZ-B09CFL	• Telescoping Hopper Access Ladder (not available with streetside sump clean-out door)	1	636.00	636.00T
EZ-B10CFL	• 10" Cabshield Extension	1	632.00	632.00T
EZ-B11CFL	• Front Body Screen Enclosure	1	444.00	444.00T
EZ-B17CFL	• Mud Flaps Forward of Tandems	1	228.00	228.00T
EZ-B18CFL	• 20# Fire Extinguisher with Bracket	1	354.00	354.00T
EZ-B20CFL	• Remote Lube Fittings for Packing Panel	1	422.00	422.00T
EZ-B26CFL	• "CAUTION" Decal on Tailgate	1	184.00	184.00T
EZ-B28CFL	• Additional Body Spring Mounts (1) Extra Set Installed Forward (Required on all Mack Chassis)	1	509.00	509.00T
EZ-B30CFL	• HD Bumper Stops - Yellow	1	295.00	295.00T
EZ-L06CFL	• 60" Forks	1	684.00	684.00T
EZ-L08CFL	• 6" Fork Bumper Pad Extensions	1	255.00	255.00T
EZ-E01CFL	• Hopper Flood Light	1	158.00	158.00T
EZ-E02CFL	• Dual Amber LED Lights (Mid-Height on Tailgate) 6" oval	1	643.00	643.00T
EZ-E03CFL	• Container Flood Light	1	158.00	158.00T
EZ-E05CFL	• Trapezoidal Reverse Lights Mounted on Body Sides	1	198.00	198.00T
EZ-H02CFL	• Powder Coat - Single Color - Non White (On Production Line) Specify Paint Color Code	1	2,421.00	2,421.00T
2016 Mack MRU	• 016 Mack MRU as per the 2015 FSB	1	134,103.00	134,103.00T
EZ-E06CFL	• Dual Cab Work Lights	1	361.00	361.00T
WEP-MM-4000B	• Minimizer 4000B Poly Spray Control Fenders for ASL, CFL, and REL	1	1,758.00	1,758.00T

Thank you for giving us the opportunity to quote for your waste equipment and parts needs. Any applicable taxes may be added or adjusted at any time to be within full compliance of the law. No warranties will be honored on any items exported outside of the United States.

Notice: ALL ESTIMATES EXPIRE 30 DAYS AFTER INITIAL ESTIMATE DATE.

SubTotal	$240,451.00
Tax (1%)	$2,404.51
Shipping	$2,500.00
Total	$245,355.51

Accepted By

Accepted Date

ORDER CODE INFORMATION (OCI)

E-Z Pack Hercules Front Loader Project: 2153

WASTE EQUIPMENT & PARTS LLC

866-228-2411

4902 South 16th Avenue, Suite E
Tampa, FL 33619
813-241-1900 / Fax 813-241-1990

1907 NW 40th Court
Pompano Beach, FL 33064
954-366-5232 / Fax 954-532-7439

www.Waste-Equip.com

ORDER CODE INFORMATION (OCI)

Option EZ-CFL-44-14FSB - E-Z Pack HERCULES COMMERCIAL FRONT LOADER

This option is for a base commercial front loader priced as per the 2014 FSB.

Option includes the following equipment:

- *Model FLOO80J44SE*
- *44 Cubic Yard Commercial Superstructure Assembly*
- *Bolt-on Lift Arm "J" Style – 10,000 Lbs Construction*
- *3.75 Cubic Yard Tailgate*
- *10 Ga. 100,000 PSI Body Side Walls*
- *Radiuses Body Floor, Side and Roof*
- *100 Gallon body Sump for Liquid Retention*
- *Bolt on Cab Shield*
- *Sliding Hopper Cover*
- *Automatic Lock / Unlock Tailgate*
- *High Mount Tailgate Lights with Center Brake Light*
- *8" Convex Mirror – Driver Side*
- *Operator In Cab Air Control – Forks / Arm*
- *Auto Pack – Packer Controls*
- *Tailgate Safety Maintenance Prop*
- *Muncie MLS Hydraulic Pump*
- *Commercial Grade Hydraulic Package*
- *Premium Packer Cylinders – 3 Year Warranty*
- *E-Z Pack Prox. Control Switches*
- *DOT Tape*
- *Factory Made Wiring Harness*
- *Front Body Spring Mounts*

WASTE EQUIPMENT & PARTS LLC

E-Z Pack
Refuse Hauling Solutions, LLC

Specifications are subject to change without notice.